

June 26, 2023

MIDDLETON ASSOCIATES INCORPORATED  
1702 W. COLLEGE AVE., SUITE E  
NORMAL, IL 61761-2793  
309/452-1271 FAX 309/454-8049

ADDENDUM NUMBER 3  
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: 2023 Saferoom Addition for MacArthur Early Childhood Center

FOR: Macomb CUSD No. 185  
323 W. Washington Street  
Macomb, IL 61455

A/E PROJECT NO: 2592 0221

ISSUE DATE: June 1, 2023

BID OPENING: Friday, June 30, 2023, 2:00 p.m., prevailing time  
323 W. Washington Street, Macomb, IL 61455

THIS ADDENDUM DOES NOT CHANGE THE BID DATE OR BID TIME.

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein. THIS ADDENDUM DOES NOT CHANGE THE BID DATE.

5. TO THE SPECIFICATIONS: Section 10 1100; Visual Display Surfaces 2.1.A.3, 2.1.B.3, 2.1.C.2: ASI shall be an equivalent manufacturer
6. TO THE SPECIFICATIONS: Section 10 2113; HDPE Toilet partitions 2.1.E: ASI is an approved equal.
7. TO THE DRAWINGS: Addendum #2, Sheet C101; South fence playground to football field: Adjust fence line to exclude guy wire from the playground area. This will adjust the offset about 15' east, extend south until it encounters the shown layout near the gate.
8. TO THE DRAWINGS: Sheet A6 Elevations and Roof Plan: Actually in southwest corner of the existing roof, there is a 4' overhang. Cut the gutter back and cap and install relocated downspout and arrange with roofing for this to be an overflow drain condition. This will require some blocking and sheet metal work to properly finish and enclose weather tight.

We will want roof tie in as proposed to redirect water to roof drain. Gutter should only catch overflow water.

9. TO THE SPECIFICATIONS: Section 05 3100; Metal Decking 2.1.A.1: Decking may be composite style in lieu of acoustical decking. Contractor option.

END ADDENDUM NO. 3